

Infrastructure Project from C level up to UPS Room 36th floor MI cable and tele/data conduits for new data center on the 36th floor to maintain office staff which includes 220 traders on the 36th floor which also included 55 executive offices and 600 work stations on the 37th & 38th floors. High end conference rooms which included Lutron Dimming System with LED high efficiency lighting, LEED Gold Certifications.

Installation of (2) 1000kw Generator with Avtron loadbank, ATS switches, Leibert UPS, System 800 amps with redundant feeders to protect and support Data Center.

